



## LOAD SUMMARY

# RIG TWELVE 19 LOADS (WITHOUT BOILER)

Depth capacity: TVD 5000m

## LOAD SUMMARY

LOAD DESCRIPTION	WEIGHT		DIMENSIONS (L X W X H)	
	KG	LBS	METRES	FEET
MAST/DRAWWORKS	65,100	143,300	12.20 x 2.40 x 3.66	40 x 8 x 12
SUBSTRUCTURE (W/O BOPS)	45,800	100,800	18.30 x 3.66 x 4.88	60 x 12 x 16
MUD PUMP (2)	39,000	85,800	12.20 x 3.80 x 3.05	40 x 12.5 x 10
MUD TANK (2)	30,800	68,000	14.35 x 3.66 x 3.05	45 x 12 x 10
COMBINATION BUILDING	33,600	74,000	16.76 x 3.66 x 2.75	55 x 12 x 9
DOGHOUSE/WATER TANK	29,800	65,600	15.24 x 3.66 x 3.66	50 x 12 x 12
RIG MANAGER SHACK	16,100	35,495	12.20 x 3.66 x 3.05	50 x 12 x 10
CONTAINER BUILDING	9,000	19,845	12.20 x 3.05 x 2.44	40 x 10 x 8
HYDRAULIC CATWALK	19,500	42,900	18.30 x 3.05 x 3.75	60 x 10 x 12.3
DRILL COLLARS/RACKS	variable	variable	variable	variable
HWDP/PIPE TUBS (5)	variable	variable	10.67 x 2.30 x 1.07	35 x 7.50 x 3.50
MATTING (20)	variable	variable	2.40 x 12.20	8 x 40
TOP DRIVE HPU	27,300	60,000	12.20 x 3.66 x 3.05	40 x 12 x 10
BOILER	18,500	40,875	12.20 x 3.05 x 3.05	40 x 10 x 10

