



LOAD SUMMARY

RIG TWO 17 LOADS (WITHOUT BOILER)

Depth capacity: TVD 2800m, MD 4500+ m

LOAD SUMMARY

LOAD DESCRIPTION	WEIGHT		DIMENSIONS (L X W X H)	
	KG	LBS	METRES	FEET
MAST/DRAWWORKS	44,750	98,660	12.20 x 2.40 x 3.5	40 x 8 x 11.5
SUBSTRUCTURE (W/O BOPS)	34,680	76,460	12.20 x 4.10 x 3.65	40 x 13.5 x 12
MUD PUMP (2)	42,000	92,600	12.20 x 3.80 x 2.90	40 x 12.5 x 9.5
MUD TANK	32,700	72,100	15.24 x 3.66 x 2.75	50 x 12 x 9
COMBINATION BUILDING	27,000	59,525	15.24 x 3.66 x 2.75	50 x 12 x 9
DOGHOUSE/WATER TANK	26,300	57,985	12.80 x 3.66 x 3.66	42 x 12 x 12
RIG MANAGER SHACK	16,100	35,495	12.20 x 3.66 x 3.05	40 x 12 x 10
CONTAINER BUILDING	9,000	19,845	12.20 x 3.05 x 2.44	40 x 10 x 8
HYDRAULIC CATWALK	25,000	55,115	18.30 x 3.05 x 3.75	60 x 10 x 12.3
DRILL COLLARS/RACKS	variable	variable	Variable	variable
HWDP/PIPE TUBS (5)	variable	variable	10.67 x 2.30 x 1.07	35 x 7.50 x 3.50
MATTING (20)	variable	variable	Variable	variable
BOILER	18,500	40,875	12.20 x 3.05 x 3.05	40 x 10 x 10

